FIRST CONGREGATIONAL PARSONAGE 305 West 2nd Street Wabasha Wabasha County Minnesota

HABS MINN, 79-WAB,

PHOTOGRAPHS

HISTORICAL AND DESCRIPTIVE DATA

Historic American Buildings Survey
National Park Service
Rocky Mountain Regional Office
Department of the Interior
P.O. Box 25287
Denver, Colorado 80225

Wabasha Historic District HABS NC. MN-66 Page 1

HISTORIC AMERICAN BUILDINGS SURVEY

First Congregational Parsonage

HABS MINN, 79-WAB,

Location:

305 West Second Street Southwest guadrant of intersection

of West Second Street and Walnut Avenue

On Lot 1 and 20 feet of Lot 2, Block

19, Original Plat of Wabasha

In Wabasha, Wabasha County, Minnesota

UTM:

15/576930E/4914740N

Ouad:

Wabasha North

Date of Construction:

1872

Remodeled in 1950's and in 1979

Present Owner:

Minnesota Department of Transportation

St. Paul, Minnesota 55155

Present Use:

Vacant

Significance:

One of Wabasha's finest examples of a frame Italianate style building. Its exterior integrity has survived throughout its service as the First Congregational Parsonage from 1872 to 1955, as a residence from 1955 to 1979, and as a chiropractic clinic

from 1979 to 1986.

Documentation prepared by:

J. R. Weimerskirch, C. P. Kachelmyer Minnesota Department of Transportation

Wabasha Historic District HABS No. MN-66 First Congregational Parsonage Page 2

HISTORICAL NARRATIVE

The Congregational Church of Wabasha was organized in February 1856, making it the second oldest organized religious group in Wabasha. The Church Turstees purchased lots 1 & 2, Block 19, original plat of Wabasha from George W. Bacon on May 1, 1866. They built their original church on lot 2 at a cost of \$1,000. It measured 22'x50' and was dedicated on October 20, 1858. That building was incorporated into the present church building in 1884. Further additions and alterations have been made in recent years to the church building.

The Parsonage was constructed on lot 1 and part of lot 2 in 1872 at a cost of \$3,600. The first occupant was Reverend C. W. Honeyman. In 1918 the Church Board authorized payment of \$1,400 for unspecified improvements to the property. This Parsonage served as a permanent residence for the church clergy until 1955. The interior of the building from the basement through the second story was extensively damaged by fire in the 1950's.

In 1955 the Parsonage building become a private residence. The Church Board sold the property to John R. and Betty Lou Flatt in 1959 for \$9,000. It was acquired by Edward J. and Jeanne C. Drury in 1966, by the American Bank of Alma in 1970, by Randall H. & Janet R. Patton for \$25,000 in 1971, by Gerald J. and Mary E. Wild for \$26,000 in 1972, and by Dr. Jay M. and Marya L. Greenberg for \$64,000 in 1979. In 1979 the interior of the building was remodeled for use as a chiropractic clinic, for which it was used until it was acquired by the Minnesota Department of Transportation in 1986.

ARCHITECTURAL INFORMATION

The First Congregational Parsonage is situated on its original location at the southwest corner of Walnut Avenue and Second Street. This two story Cubiform Italianate style frame building has a low pitched hip roof. The side hall plan has a simple rectangular front portion with a rear section slightly offset from the front forming a T plan. The building has horizontal lap siding with corner boards. The eaves are supported by regularly spaced brackets. Dimensions of the front portion of the original building are 26'6"x31' and of the rear portion are 21'x18'.

The front entry, facing on Second Street, has a hip roof and simple pillars that replace the original, more decorative, open porch. The four panel entry door has a clear glass transom light.

Wabasha Historic District HABS No. MN-66 First Congregational Parsonage Page 3

Sash windows on the front (north) and on the east and west facades of the front portion of the building are narrow rectangles set in segmental arch wood surrounds with infill at the tops of the arches. Paired windows on the first and second stories offset the main entrance on the front facade. The east facade of the front portion has a paired sash, cantilever bay with a bracketed cornice on the lower story with a paired sash above it on the second story. The rectangular double hung windows on the rear section are set in simple wood frames.

An attached garage has been added on the southeast corner of the building. An open arcade behind the garage joins a one story screen porch attached to the southwest corner of the building.

The interior of this building has been extensively remodeled in recent years, especially due to an extensive fire in the 1950's. Charred timber beams and joists still remain in the basement, supplemented with new lumber.

FUTURE DISPOSITION

The property on which this building is situated is needed on which to construct a portion of the approach to a new bridge to carry Trunk Highway 60 over the Mississippi River between Minnesota and Wisconsin. This building will be moved by the Minnesota Department of Transportation to a new site within the City of Wabasha which has been reviewed and found acceptable by the Minnesota State Historic Preservation Officer. The building will be placed on a new foundation, utility services will be restored, and the building will be offered for sale for preservation.

HABS NO. MN-66 First Congregational Parsonage Main Floor Plan 1" = 10' Scale: page 4 Ceiline Ht. Room No. Living Room Dining Room Kitchen Bed Reem **Bod Room** Beth 10 Hell 8 Parch Claset 2 Stars Room Amusement Ream 8 Attached Garege 4 OFFICE 10 10 EXAM. RM. 8/2 LAB BASEMENT: Floor thickness. Height: Top of Roor to top of foundation . Size Sa. Ft. Ht. Cube SUPERSTRUCTURE: Height: Top of foundation to Eaves to ridge Sixe Sq. Ft. Total cubic mentant Chimney slaps

Floor

Wells

Condition

Siee

Aree


Wabasha Historic District

\$3

. AM EOUS BUILDINGS

Foundation

HABS NO. MN-66
First Congregational Parsonage
Second Floor Plan
Scale: 1" = 10'
page 5



7 48,000